

# Case Study

**Customer:** Tilbury Docks Authority

**Location:** Tilbury, London

**Task:** To remove and containerise approximately 15 tonnes of decomposing sardines and resultant fluids from a refrigeration unit abandoned for six months.

- Erection of a temporary waterproof bund around the unit to contain any leakage or run-off
- Removal of all boxes by hand and transfer to airtight transport containers
- Removal of all waste for safe disposal off-site
- High-pressure water jet cleaning of entire interior of the refrigeration unit.

The job was completed within three days.

**Value: Confidential**

